

OFFICE OF THE ESTATE OFFICER,

SRI KARAN NARENDRA AGRICULTURE UNIVERSITY, JOBNER-303329 Distt. Jaipur (Raj.) Phone:-01425254982

No: F/ 13()/SKNAU/EO/Quotation/ 2024-25/ 421-25

Request for Quotation

Sealed Quotation are invited from the Registered Contractors to execution of the following works in the attached 'H' schedule. The quotation will be accepted up to **22.07.2024 at 12.00 P.M.** and will be opened on the same day at **12.15 P.M.** by the Estate Officer. Relevant registration certificate of contractor must be enclosed with 'H' schedule. The Estate Officer has all right to accept/reject any quotation without assigning the reason. Quantity can be increase/decrease.

Name of work:- Additional work of repair & renovation of office building at KVK, Navgaon, Alwar.

Estimated Cost: 95,000/-

Work Completion period : One Month.

ESTATE OFFICER

/ nother

Date: 15.07.2024

Copy to:-

- 1. The PS to the Vice Chancellor, SKNAU, Jobner.
- 2. The Comptroller, SKNAU, Jobner.
- 3. Office Incharge, CIMCA for upload on website of the University.
- AEn Jobner.
- 5. The Cashier/ Accounts, Estate Office, SKNAU, Johner.
- 6. Notice Board- Office/
- 7. M/s.....
- 8. M/s.....
- 9. M/s.....

ESTATE OFFICER

Jackson

OFFICE OF THE ESTATE OFFICER SRI KARAN NARENDRA AGRICULTURE UNIVERSITY,

JOBNER-303329 Distt. Jaipur (Raj.)

Name of work - Additional work of Repairs & Renovation work of Office Building at KVK, Navgaon, Alwar. Rates Based on - BSR PWD 2022.

"G" schedule

BSR Item No	S.No	Particulars	Quantity	Unit	Rate	Amount	Total Amount in words
Item No	•						
12.3.1	1	Plaster on new surface on walls in cement sand mortar 1:6 including racking of joint etc. complete fine finish: 25 mm thick	127.00	Sqm	211.00	26797.00	Rupees Twenty Six Thousand Seven Hundred Ninety Seven Only
9.19.3	2	Providing and fixing steel glazed doors windows and ventilator shutters of standard rolled steel section (IS 1038-1983) joints mitred and welded with steel lugs 13x3mm, 10cm. long embedded in cement concrete block 15x10x10cm. of 1:3:6 (1cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size) or with wooden plugs and screws or rawl plugs and screws with fixing clips or with bolts and nuts as required including providing and fixing of plain glass panes 4mm thick with cooper glazing clips and special metal sash putty of approved make or metal beading with screws complete including priming coat of approval steel primer, excluding the cost of metal beading and other fitting except necessary hinges of pivots steel handles peg stay etc. as required: Windows side hung /Ventilators top or centre hung (openable)		Sqm	3135.00	6583.50	Rupees Six Thousand Five Hundred Eighty Three and Fifty Paise Only
9.26	3	Supplying and fixing fixed wire gauge of 14 mesh x 24 gauge to the metal frame of rolled section by metal beading 20x3mm with suitable screw at not exceeding 150mm distance.	2.00	Sqm	617.00	1234.00	Rupees One Thousand Two Hundred Thirty Four Only
9.27	4	Providing and fixing Square bars or other flat welded to window, ventilatiors etc.	27.52	Kg	65.00	1788.80	Rupees One Thousand Seven Hundred Eighty Eight and Eighty Paise Only
12.37.1	5	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade including all scaffolding: New work (two or more coats) over and including scrapping and priming coat with cement primer.	127.00	Sqm	75.00	9525.00	Rupees Nine Thousand Five Hundred Twenty Five Only
12.46.2	6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: One or more coats on old work.	25.00	Sqm	34.00	850.00	Rupees Eight Hundred Fifty Only
13.24	7	Labour charges for repair to door / window without using any material such as applying randha (finishing) tightening of bolts & screw etc.	25.00	Sqm	220.00	5500.00	Rupees Five Thousand Five Hundred Only
9.2	8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting (height upto 10 m), fixing in position and applying a priming coat of approved steel primer all complete:	150.00	Sqm	81.00	12150.00	Rupees Twelve Thousand One Hundred Fifty Only
6.17.2	9	Supplying and fixing in walls machine cut and polished stone shelves, tands and in CM 1:3 with machine cut edges: Sand or other approved stone 50mm thick.	1.75	Sqm	673.00	1177.75	Rupees One Thousand One Hundred Seventy Seven and Seventy Five Paise Only

				Total amount		94389.05	Rupees Ninety Four Thousand Three Hundred Eighty Nine and Five Paise Only
S-3.17.3	14	P&F rigid PVC pipe fittings (IS: 4985 mark) of approved quality /make including joining the pipe with solvent cement rubber ring and lubricant: Plain Tee:75mm dia	6.00	Nos	114.00	684.00	Rupees Six Hundred Eighty Four Only
		including joining the pipe with solvent cement rubber ring and lubricant: Bend 87.5 :75mm dia					Only
S-3.17.9	13	making good the wall: P&F rigid PVC pipe fittings (IS: 4985 mark) of approved quality /make	25.00	Nos	97.00	2425.00	Rupees Two Thousand Four Hundred Twenty Five
		of approved make with complete fittings C.I. brackets duly painted, brass ball cock with ball (IS: 1703 mark) complete including cutting and					Only
S-1.20.2	12	P & F Low level Flushing Cistern of 10 litres capacity (IS: 2556 mark)	2.00	Nos	1291.00	2582.00	Rupees Two Thousand Five Hundred Eighty Two
		mm thick masonry in CM 1:6, 10 Cm. thick cement concrete 1:5:10 in foundation, 20 mm thick inside plaster in CM 1:6, finished with floating neat cement, 50mm thick M-15 grade C.C. flooring, making channels, 80mm thick stone slab covering with 40mm thick M-15 grade C.C. flooring, Cement cover with frame of 450mm dia, earthwork etc. complete as per design including disposal of surplus earth within 50 mtr. lead.					Only
S-3.19.1	11	on 12mm (Av.) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) jointing with white cement mortar 1:2 (1white cement : 2 marble dust) with pigment to match the shade of the marble slab including grinding, rubbing and polishing complete. Construction of manhole in all type of soil inner size 90 X 60 Cm. 300	2.00	Nos	5489.00	10978.00	Rupees Ten Thousand Nine Hundred Seventy Eight
7.5.1 (iii)	10	Providing and fixing Granite stone slab mirror polished and machine edge cut in walls, pillars, steps, Shelves, Sills Counters, Floors etc. laid	1.00	No.	12114.00	12114.00	Rupees Twelve Thousand One Hundred Fourteen Only

Estate Officer

Signature of Contractor

Estate Officer