



**OFFICE OF THE ESTATE OFFICER,  
SRI KARAN NARENDRA AGRICULTURE UNIVERSITY,  
JOBNER-303329 Distt. Jaipur (Raj.) Phone :-01425254982**

No: F/ 13( )/SKNAU/EO/Quotation/ 2024-25/ 472

Date: 22.07.2024

**Request for Quotation**

Sealed Quotation are invited from the Registered Contractors to execution of the following works in the attached 'H' schedule. The quotation will be accepted up to **29.07.2024 at 12.00 P.M.** and will be opened on the same day at **12.15 P.M.** by the Estate Officer. Relevant registration certificate of contractor must be enclosed with 'H' schedule. The Estate Officer has all right to accept/ reject any quotation without assigning the reason. Quantity can be increase/ decrease.

**Name of work:- Providing and laying LT Cable at University Adm. building, SKNAU, Jobner.**

**Estimated Cost: 48,000/-**

**Work Completion period : Seven Days.**

ESTATE OFFICER

Copy to:-

1. The PS to the Vice Chancellor, SKNAU, Jobner.
2. The Comptroller, SKNAU, Jobner.
3. Office Incharge, CIMCA for upload on website of the University.
4. AEn Jobner.
5. The Cashier/ Accounts, Estate Office, SKNAU, Jobner.
6. Notice Board- Office/
7. M/s.....
8. M/s.....
9. M/s.....

ESTATE OFFICER

**OFFICE OF THE ESTATE OFFICER  
SRI KARAN NARENDRA AGRICULTURE UNIVERSITY,  
JOBNER-303329 Distt. Jaipur (Raj.)**

Name of Work :- Providing and laying LT Cable at University Adm. building, SKNAU, Jobner.  
Based on:- P.W.D. B.S.R. 2022 & Electric BSR 2022

**"G" schedule**

BSR Item No	S.No.	Particulars	Quantity	Unit	Rate	Amount	Total Amount in words
1.8	1	Earth work in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift up to 1.5 Mtr. including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed within a lead of 50 meter. All kinds of soil	40.00	Cum	178.00	7120.00	Rupees Seven Thousand One Hundred Twenty Only
E-11.2.4.3	2	Providing & Laying P.V.C. / XLPE insulated & P.V.C. sheathed Armoured Aluminium cable confirming to IS:1554 P-I / IS :7098 P - I of 1.1 KV with H4- Grade electrolytic aluminium conductor confirming to IS 8130 of purity >99.6 %, round / flat strip armouring of cables, Inner / outer sheath confirming to IS:5831 in existing RCC / Hume / Stoneware / PVC pipe/ open duct/cable trench / Cable tray(with cable tie) including testing etc. as required of following size. OEM must have it's own in house NABL accredited Laboratory for testing procedure as per IS:10810.For additional technical parameters of product / work refer Annexure 'A' attached with this BSR: 16.0 Sq. mm: 4 core	175.00	Mtr	232.00	40600.00	Rupees Forty Thousand Six Hundred Only
				<b>Total amount</b>		47720.00	Rupees Forty Seven Thousand Seven Hundred Twenty Only



**Estate Officer**

I/we beg to tender as per ..... % above /below / of the "G" Schedule

Signature of Contractor

**Estate Officer**