



OFFICE OF THE ESTATE OFFICER,
SRI KARAN NARENDRA AGRICULTURE UNIVERSITY,
JOBNER-303329 Distt. Jaipur (Raj.) Phone :-01425254982

No: F/ 13()/SKNAU/EO/Quotation/ 2025-26/ 342-48

Date: 20.05.2025

Request for Quotation

Sealed Quotation are invited from the Registered Contractors to execution of the following works in the attached 'H' schedule. The quotation will be accepted up to **27.05.2025 at 12.00 P.M.** and will be opened on the same day at **12.15 P.M.** by the Estate Officer. Relevant registration certificate of contractor must be enclosed with 'H' schedule. The Estate Officer has all right to accept/ reject any quotation without assigning the reason. Quantity can be increase/ decrease.

Name of work:- Additional work of Construction of Boundary Wall at Research Farm, SKNAU, Jobner.

Estimated Cost: 73,000/-

Work Completion period : Fifteen Days.

ESTATE OFFICER

Copy to:-

1. The PS to the Vice Chancellor, SKNAU, Jobner.
2. The Comptroller, SKNAU, Jobner.
3. Office Incharge, CIMCA for upload on website of the University.
4. AEn Jobner.
5. The Cashier/ Accounts, Estate Office, SKNAU, Jobner.
6. Notice Board- Office/
7. M/s.....
8. M/s.....
9. M/s.....

ESTATE OFFICER


OFFICE OF THE ESTATE OFFICER
SRI KARAN NARENDRA AGRICULTURE UNIVERSITY,
JOBNER-303329 Distt. Jaipur (Raj.)

Name of Work :- Additional work of Construction of Boundary wall at Research Farm, SKNAU, Jobner.

Based on:- P.W.D. B.S.R. 2022

"G" schedule

BSR Item No	S.No.	Particulars	Quantity	Unit	Rate	Amount	Total Amount in words
14.9.2	1	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: In cement mortar.	1.00	Cum	641.00	641.00	Rupees Six Hundred Forty One Only
9.36.2	2	Supplying and fixing of chain link fencing with angle iron posts 50x50x6mm placed at every 3 Mtr. apart 30 Cm. in ground embedded in cement concrete 1:3:6 (30x30x45 Cm.) corner and every tenth post to be strutted with (50x50x6 Cm.) angle iron provided and fixed and fitted with posts including earth work in excavation etc. complete with chain link size. 75mm x 75mm x 3.15mm.	90.00	Sqm	565.00	50850.00	
9.33	3	Add or deduct for each wire line over basic item	180.00	Mtr	12.00	2160.00	Rupees Two Thousand One Hundred Sixty Only
9.35	4	Add for using galvanized barbed wire instead of black barbed wire	180.00	Mtr	0.60	108.00	Rupees One Hundred Eight Only
9.37	5	Providing and fixing concertina coil fencing with required dia 610 mm (having 15 nos. round per 6 metre length) up to 3m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. stud tied with GI staples and GI clips to retain horizontal including necessary bolts or GI barbed wire tied to angle iron all complete as per direction of Engineer In Charge with reinforced barbed tape (R.B.T.)/Spring core(2.5 mm thick) wire of high tensile strength of 165 kg/sq.mm with tape (0.52 mm thick) and weight 43.478 gm/metre (Cost of MS angle, CC block shall be paid extra)	44.00	Mtr	266.00	11704.00	Rupees Eleven Thousand Seven Hundred Four Only
9.1	6	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting (height upto 10 m), fixing in position and applying a priming coat of approved steel primer all complete.	90.00	Kg.	72.00	6480.00	Rupees Six Thousand Four Hundred Eighty Only
12.46.1	7	Painting with enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	14.00	Sqm	69.00	966.00	Rupees Nine Hundred Sixty Six Only
				Total amount		72909.00	Rupees Seventy Two Thousand Nine Hundred Nine Only



Estate Officer

I/we beg to tender as per % above /below / of the "G" Schedule

Signature of Contractor

Estate Officer